

15.185.01831.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Co.

Complete Address Box 1070 Gread Bend, Ks 67530

Lease Name R. C. Gates Well No. 11

Location SE/SW/NW Sec. 35 Twp. 21s Rge. 13 (E) (W) W

County Stafford Total Depth 3726

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 E. 6th Ellinwood, Ks License No. 396

Operation Completed: Hour 11:AM Day 28 Month 1 Year 1970

The above well was plugged as follows:

282 ft. of 8 5/8 surface pipe cemented with 225 sacks cement. Did
circulate. 3725 ft. of 5 1/2 long string cemented with 175 sacks cement.
Top perforated. 3662 ft sand back to 3650 and 5 sacks cement with
bailer. 2510 ft of 5 1/2 pulled, plug and mud from 3620 to 280 ft. 10 ft
rock bridge to 270 ft run, 5 sacks cement with bailer, bailed hole
to top of cement. 25 sacks cement from 270 ft to 180 ft mud from 180
ft to 40ft. Rock bridge & 10 sacks of cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Russell B. Schuster
Well Plugging Supervisor

INVOICED

DATE 1/30/70
INV. NO. 1329-w