

15.185.20587.0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Woodman & Iannitti Drlg Co

Complete Address Box 308 Great Bend, KS

Lease Name Gates Well No. 1

Location E/2 NW/NW Sec. 35 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3697

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering Inc

Address Box 698 Great Bend, KS License No. 670

Operation Completed: Hour 11:30 AM Day 31 Month 12 Year 1975

The above well was plugged as follows:

261 ft 8 5/8 surface cemented with 210 sacks. 3680 ft 5 1/2 long string
cemented with 100 sacks. Top perf. 3697 ft. Push plug to 3600 ft,
5 sacks cement with bailer. Pulled 2900 ft 5 1/2. Pump 2 sacks hulls,
10 sacks gel, 100 sacks cement to surface.

Pumped by Sun Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

NOTICED
DATE 1-5-76
INV. NO. 2521-W

Signed: [Signature]
Well Plugging Supervisor