

K
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1966

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
STATE CORPORATION COMMISSION

Operator's Full Name Petroleum, Inc., c/o Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Hufford "A" (Hazel South Flood Unit Well No. # 4

Location SW NE NW # 2-3 Sec. 28 Twp. 21 Rge. 13 (E) (W)

County Stafford Total Depth 3734'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Puller, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:30AM Day 25th Month Feb. Year 1966

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cemented with 175 sacks. 3733' of 5 1/2" long
string, cemented with 100 sacks. Plug back TD 3594'. Top perferation 3388'.
Pipe was parted at 740', and bottom was not plugged off. 740' of 5 1/2" long
string was recovered from the hole. Fluid was up in the hole. rock bridge was
set on pipe at 740' to 730', and cemented with 5 sacks, through the dump bail-
er. Bridge plug was pushed in fluid to 200', rock bridge from 200' to 190'.
8 sacks of cement was mixed in a barrel, and put on plug at 190', through the
dump bailer, and let set over-night. Next morning hole was bailed dry, and 17
sacks of cement was added to the plug. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/1/66

INV. NO. 2985-W