

P KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1966

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc., c/o Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Hufford "A" Well No. # 6

Location NE SW NW Sec. 28 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3737'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 9:30AM Day 25th Month Feb. Year 1966

The Above well was plugged as follows:

204' of 8 5/8" surface pipe, cement circulated. 3729' of 5 1/2" long string,
cemented with 125 sacks. Plug back TD 3600'. Top perferation 3380'. Bottom
of the hole was sanded to 3325', and cemented with 5 sacks, through the dump
bailer. 2910' of 5 1/2" long string was recovered from the hole. Fluid was up in
the hole. Bridge plug was pushed to 200', rock bridge from 200' to 190'. 10
sacks of cement was mixed in a barrel, and put on plug at 190', through the
dump bailer, and let set over-night. Next morning hole was bailed dry, and
15 sacks of cement was added to the plug. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/1/66

INV. NO. 2486-4