

*Me*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

FEB 18 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum, Inc., c/o Pipe Pullers, Inc.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name Hazel L-KC Unit (Hufford A-5) Well No. # 2-9

Location SW SW NW Sec. 28 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3752'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Puller, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 9:30 AM Day 15th Month Feb. Year 1966

The Above well was plugged as follows:

165' of 8 5/8" surface pipe, cemented with 175 sacks. 3751' of 5 1/2" long  
string, cemented with 125 sacks. Plug back to 3518'. Top perforation 3380'.  
Bottom plug was pushed to 3375', 50' of sand, and cemented with 5 sacks,  
through the dump bailer. 2911' of 5 1/2" long string was recovered from the  
hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 165',  
rock bridge from 165' to 155'. 6 sacks of cement was mixed in barrel, and  
put on plug at 155', through the dump bailer, and let set over-night. Next  
morning hole was bailed dry, and 19 sacks of cement was added to the plug.  
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented  
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 2/18/66  
INV. NO. 2738-W