

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC -1 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name Hazel L-KC Unit #4-11(P.L.Keenan) Well No. "A" # 2

Location NE NW SW Sec. 28 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3746'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:30AM Day 27th Month Nov. Year 1965

The Above well was plugged as follows:

205' of 8 5/8" surface pipe, cement circulated with 175 sacks. 3745' of 5 1/2"
long string, cemented with 125 sacks. Plug back to 3455'. Top perforation
3377'. Bottom of the hole was sanded to 3370', and cemented with 5 sacks,
through the dump bailer. 3018' of 5 1/2" long string was recovered from the hole.
Fluid was up in the hole. Bridge plug was pushed in fluid at 205'. rock bridge
from 205' to 195'. 5 sacks of cement was mixed in barrel, and put on plug at
195', through the dump bailer, and let set over-night. Next morning hole was
bailed dry, and 20 sacks of cement was added to the plug. Hole was filled with
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 12-1-65

INV. NO. 23 07-W