

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued September 6, 1967.

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1967

9-25-67

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Great Bend Pipe & Supply Company, Inc. Wichita, Kansas

Complete Address: Drawer "B", Great Bend, Kansas 67530

Lease Name J. Morrison Well No. # 6

Location CNL SW SE Sec. 28 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3730'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:00 AM Day 27th Month Sept. Year 1967

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cement circulated. 3728' of 5 1/2" long string, cemented with 125 sacks. This is an open hole. Bottom of the hole was sanded to 3700', and cemented with 5 sacks, through the dump bailer, with cement from 3700' to 3660'. 3102' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 280', bridge plug and rock bridge from 280' to 270'. 5 sacks of cement was mixed in a barrel, and put on plug at 270', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 20 sacks of cement was added to the plug, with cement from 270' to 195'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/29/67

INV. NO. 6410-u