

State of Kansas



GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS
JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1959

CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 5-25-59, 1959, authorized the following plugging operation:

Operator's Full Name: K & E Drg Co

Complete Address: 719 Union Center Wichita, Kans

Lease Name: Ruder Well No. 1

Location: SE SE NE Sec. 18 Twp. 15 Rge. 18 (E) (W)

County: Ellis Total Depth: 3665

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Circulate with heavy mud, set plug at 400', displace 35 sax cement through drill pipe, mud to 180', set plug and 35 sax cement through drill pipe, mud to 40', set plug, hulls and 10 sax cement to bottom cellar.

Very truly yours,

Signed: *Jewel M. Ogden*
Conservation Division Agent

DRILLER'S WELL LOG

OPERATOR: K & E AND BOA

WELL NAME: #1 RUDER

719 Union Center
Wichita 2, Kansas

LOCATION: SE SE NE, Sec 18-15S-18W
ELLIS COUNTY, KANSAS

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: May 16th, 1959

CASING RECORD: 8-5/8" @ 243' (160 sx)

COMPLETED: May 25th, 1959

ELEVATION: 2037' KB

ROTARY TOTAL DEPTH: 3670'

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Shale	60
Shale & Shells	390
Shale	640
Sand	870
Shale	1195
Anhydrite	1240
Shale	1450
Shale & Shells	1690
Salt & Shale	1820
Shale & Shells	1880
Lime & Shale	2250
Lime	2340
Lime & Shale	2870
Shale & Lime	2995
Lime	3540
Lime & Conglomerate	3616
Conglomerate	3665
R.T.D.	3665

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1959
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS
County of SEDGWICK ss:

I, Dale Silcott, of K&E DRILLING, INC. upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 28th day of May, 19 59

Patricia M. Edwards
Patricia M. Edwards, Notary Public.

My Commission expires: August 11th, 1962.

PLUGGING
FILE: SEC 18 T 15 R 11W
BOOK PAGE 41 LINE 31

