

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 211 North Broadway
 Wichita, Kansas

FILE NO. 110-36LOCATION NW SE NESEC. 4 TWP. 15 RGE. 18 W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. Z-1 Lease _____ Ruder _____Operator National Co-op Ref Assn Address 305 Rule Bldg Wichita, KansField _____ County EllisTotal Depth 3680 Feet.Plugging Contractor Ace Pipe Pulling CoPlugging Contractor's License No. 2

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3679' with 100 sax
 cement behind - P.B. to 3390', perforated at 3363'

Filled with sand to 3350', set 4 sax cement with dump bailer,

pulled 3130' 5 1/2" - pumped hole full mud (50 sax Gel), pumped

cementing plug to 200', followed by 65 sax cement - Cement 200'

to 0'.

Mudding and cementing by Globe Cementing Co.

District Conservation Agent

Date 11-3-56

PLUGGING			
FILE	SEC <u>4</u>	T. <u>15</u>	R. <u>18 W</u>
BOOK	PAGE <u>110</u>	LINE <u>36</u>	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV - 5 1956
 CONSERVATION DIVISION
 Wichita, Kansas