

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Edward P. Leiker

Complete Address: Munjor Route Box 17 Hays, Kansas

Lease Name Leiker "A" Well No. 2

Location C N/2 SE NW Sec. 2 Twp. 15 Rge. 18 (E) (W) X

County Ellis Total Depth 287'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: OWNO Could't drill cement out of old hole
below 8 5/8 csg.

Plugging Contractor: Gabbert-Jones Drilling Co.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 11 A Day 6 Month 4 Year 1967

The Above well was plugged as follows:

RTD 287' 151' of 8 5/8 csg already set.

Gunned pits, circulated heavy mud, set cementing plug at 150' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 40' set cementing plud, 1/2 sc hulls and 8 sc cement to

base of cellar. Plugged rat hole with 2 sc cement,

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lee F. Massey
Well Plugging Supervisor

DATE 4/11/67

INV. NO. 5039-W