

15.185.30041.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Murfin Drilling Company

Complete Address: 617 Union Center, Wichita, Kansas

Lease Name Fischer Well No. # 1

Location NE NW NE Sec. 31 Twp. 21 Rge. 12 (E) W

County Stafford Total Depth 3666'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company

Address: 617 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 10:00PM Day 8th Month August Year 1965

The Above well was plugged as follows:

249' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid
level in the hole was at 100'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 230', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-12-65

INV. NO. 1621-W