

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-185-20993.0000 (of this well)

Operator's Full Name Arrowhear Pet., Inc.

Complete Address 400 N. Woodlawn, Suite 29, Wichita, Ks. 67208

Lease Name W. Fischer Well No. 1

Location NE SW NE Sec. 31 Twp 21s Rge. 12 (E) (W) X

County Stafford Total Depth 3702

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67527 License No. 683

Operation Completed: Hour 1:15 Day 11 Month 6 Year 1980

The above well was plugged as follows:

210' 8 5/8" casing. 4 1/2" casing set at 3702' w/125 sax cement. Plug
back to 3636'-Top pref's at 3626' to 3628'-Sand back to 3600'-Top
sand w/4 sax mixed cement w/dump bailer-Pull 3200' casing-Allied
mixed & pumped 8 sax hulls-25 sax gel-100 sax 50/50 posmix cement
w/4% gel & 3% cc in 8 5/8" casing to top of casing. Shut (in CW/1750#)
pressure.

JUN 13 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6-13-80
INV. NO. 2354W