


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15.051.00343.00.00
R
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County. Sec. 18 Twp. 15 Rge. 18 (E) W (W)
Location as "NE/CNW/SW" or footage from lines CS/2 SE SE
Lease Owner K & E Drilling, Inc. *W. Bow*
Lease Name Linenberger #1 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-12-59 _____ 19____
Plugging completed 10-17-59 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	231'	none
				5-1/2"		3026'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3640' and found it open. Filled w/sand to 3635' and dumped 4 sacks of cement with bailer. Pulled 78 jts of 5 1/2" casing, well started flowing, pumped in 40 sacks of mud, pulled rest of casing and squeezed well with 150 sacks of cement. Mudded hole to 15' and ran 5 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

NOV 3 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 19 59

My commission expires 9-27-62

Thomas V. Dwyer
Notary Public.



DRILLER'S WELL LOG

OPERATOR: K&E & BOA
719 Union Center
Wichita 2, Kansas

WELL NAME: #1 LINENBERGER
LOCATION: 110'N & 110'E of
SW SW SE, 18-158-180
ELLIS COUNTY, KANSAS

CONTRACTOR: K&E DRILLING, INC.
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: July 23rd, 1959

CASING RECORD: 8-5/8" @ 231' (175 ss cnt)
5-1/2" @ 3635 1/2' (180 ss cnt)

COMPLETED: July 31st, 1959

ELEVATION: 2035' KB, 2033' DF

ROTARY TOTAL DEPTH: 3640'

PRODUCTION: unknown but pipe set.

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface soil & Clay	85
Sand	110
Shale & Shells	231
Shale & Red Bed	590
Sand	800
Shale & Red Bed	1200
Anhydrite	1245
Shale & Shells	1880
Lime & Shale	2455
Shale & Lime	2630
Lime & Shale	2865
Lime	3640
R.F.D.	3640'

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1962

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Dale Silcott, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott

Subscribed and sworn to before me this 4th day of August, 1959

Patricia M. Edwards

Notary Public.

My Commission expires: August 11th, 1962

