


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 3 Twp. 15 Rge. 18 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW $\frac{1}{4}$ /SW $\frac{1}{4}$ /SE $\frac{1}{4}$

Lease Owner Nadel and Gussman

Lease Name Wiesner Well No. A-#1

Office Address Box 106, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19

Plugging commenced 6-10 19 57

Plugging completed 6-14 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3626' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,682'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into TD 3626'.  
Plugging started 6-10-57. Finished 6-14-57.  
Plugged off bottom with sand to 3600' and dumped 4 1/2 sacks cement with bailer. Shot 5 1/2" casing at 2,682'. Squeezed well with 40 sacks gel mud and 150 sacks cement. Well completed.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of June, 1957.

My commission expires November 8, 1960.

Betty L. Edman  
STATE CORPORATION COMMISSION Notary Public.

JUN 19 1957

PLUGGING RECORD  
FILE SEC. 3  
BOOK PAGE  
CONSERVATION DIVISION  
Wichita, Kansas

ROTARY DRILLING LOG

Company: Nadel and Gussman  
Great Bend, Kansas

Location: Wiesner A-#1  
SW $\frac{1}{4}$  of NE $\frac{1}{4}$  of SE $\frac{1}{4}$   
Sec. 3-E15-R18  
Ellis, Kansas

Contractor:

Casing Record:

Set 321 ft 8 5/8" OD 28#  
Cemented w/175 sacks  
Run 11 $\frac{1}{4}$  joints 5 $\frac{1}{2}$ " OD 11#  
J-55 Seamless Spang Casing  
8 RD Thread Range Two  
Set at 3,61 $\frac{1}{4}$  ft. cemented  
w/150 sacks  
Backer Two stage tool  
Set at 1225' Spotted 1000  
BBl of Kenpak behind the casing, throw Dakota Sand

LOG

Top Anhydrite	1210'	
Top Heebner /shale	3272'	) -1247'
Top Tornoto	3292'	) -1267'
Top Lancing K.C.	3319'	) -1294'
Base K.C.	3553'	) -1528'
Conglomerate	3590'	) -1569'
Simpson Green Shale	3609'	) -1584'
Top Arbuckle	3613'	) -1588'
Rotary T.D.	3617'	) -1592'

5 $\frac{1}{2}$ " O.D. Set at 3614'. One ft. in Arbuckle 3 ft off bottom

Drilled 3617' to 3619'; made 35 gal. of free oil per hour

Drilled 3619' to 3623', no increase of oil, no water.

STATE GEOLOGICAL SURVEY

JUN 12 1957

PLUGGING  
SEC. 3 T. 15 R. 18W  
PAGE 19 LL 10

CONSERVATION DIVISION  
Wichita, Kansas