

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Bitting Building
Wichita, Kansas

Ellis County. Sec. 30 Twp. 15 Rge. (E) 17 (W)

Location as "NE/CNW/SE/SW" or footage from lines NE NE SW
Lease Owner Jones, Shelburne & Farmer, Inc.
Lease Name Leiker A Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 12-18 1953
Application for plugging filed 12-18 1953
Application for plugging approved 12-18 1953
Plugging commenced 12-18 1953
Plugging completed 12-18 1953
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elden Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3592 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	165	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Hole filled to 400 feet with heavy mud
- 100 sacks cement mixed and pumped into hole to 97 feet with Globe Cement Co.
- Hole filled to within 20 feet of top with heavy mud
- Halliburton plug pushed to 20 feet
- Hole filled to top with cement

1-5-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jones, Shelburne & Farmer, Inc.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
John O. Farmer (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1953

Bonnie Perryhill
Notary Public.

My commission expires April 23, 1956



GABBERT-JONES DRILLING COMPANY
WICHITA, KANSAS
DRILLERS WELL LOG

ALEX LEIKER #1
NE NE SW, SECTION 30-15-17
ELLIS COUNTY, KANSAS
COMMENCED 11-30-53
COMPLETED 12-17-53

DEPTH		FORMATION	REMARKS
FROM	To		
0	440	SHALE & SHELLS	
440	530	SHALE	
530	995	SHALE & SHELLS	RAN 1000' of 8 5/8" CASING, CEMENTED AT 995' w/475 SACKS CEMENT.
995	1115	SHALE & SHELLS	
1115	1145	ANHYDRITE	
1145	1718	SHALE	
1718	1860	SHALE & LIME	
1860	1990	BROWN LIME & SHALE	
1990	2170	LIME	
2170	2295	LIME & SHALE	
2295	2350	LIME	
2350	2490	LIME & SHALE	
2490	2995	SHALE	
2995	3115	LIME & SHALE	
3115	3333	LIME	
3333	3350	LIME & SHALE	
3350	3552	LIME	
3552	3557	LIME & CHERT	
3557	3592	LIME	
3592	TD		DRY & ABANDONED

EXECUTED THIS 21ST DAY OF DECEMBER, 1953

C. L. Gabbert

STATE OF KANSAS)
COUNTY OF SEDGWICK)

SS
JAN 5 - 1954
CONSERVATION DIVISION
WICHITA, KANSAS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 21st DAY OF December, 1953 PERSONALLY APPEARED C. L. Gabbert TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 10-27-54

Sumner E. Hall
NOTARY PUBLIC

PLUGGING
FILE SEC. 80 T 15 R 17W
BOOK PAGE 3 LINE 14