


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

ELLIS County. Sec. 19 Twp. 15S Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines W/2 NW/4 NW/4
Lease Owner Dane G Hansen, Trust
Lease Name Leiker Well No. 1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 16 19 65
Application for plugging filed " " 19
Application for plugging approved " " 19
Plugging commenced " " 19
Plugging completed " " 19
Reason for abandonment of well or producing formation Too low structurally



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	282'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
FILLED HOLE WITH HEAVY MUD TO 540'. SET PLUG WITH 25 SX CEMENT, FILLED WITH HEAVY MUD TO 240'. SET PLUG WITH 1/2 SX HULLS & 20 SX CEMENT. FILLED WITH HEAVY MUD TO 40'. SET PLUG WITH 1/2 SX HULLS & 10 SX CEMENT. FILLED TO TOP OF CSG.


RECEIVED
NOV 29 1965
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor C-G DRILLING CO. (If additional description is necessary, use BACK of this sheet)
Address 107 Rule Bldg.
Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. F. Galloway (employee of owner) or owner/proprietor of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G F Galloway
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19 day of November, 19 65
My commission expires May 20, 1967
Vicky Jacobs
Notary Public.



WELL LOG *R. G. S.*

OPERATOR: DANE G HANSEN, TRUST
 WELL NAME: LEIKER #1 LOCATION: W/2 NW/4 NW/4 19-15S-17W
 COUNTY: ELLIS STATE: KANSAS
 WELL COMMENCED: 11/7/65 WELL COMPLETED: 11/16/65
 ELEVATION: 2021 K.B. TOTAL DEPTH: 3633'
 PRODUCTION: Dry & abandoned RIG NO: 1
 CASING - 8-5/8": 282' w/200 sx cmt. (14 jts.)
 5-1/2": _____

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	282	Sand-Shale		
282	605	Shale		
605	815	Sand		
815	1182	Red Bed-Shale	1000' - 3/4°	
1182	1220	Anhydrite		
1220	1580	Shale-Shells	1500' - 3/4°	
1580	1860	Shale-Shells		
1860	3355	Lime-Shale	2500' - 3/4°	
3355	3633	Lime	3000' - 3/4°	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 29 1965
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By *G. F. Galloway*
 G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 19th day of November, 1965.

My comm. exp: May 20, 1967

Vicky Jacobs
 Vicky Jacobs - Notary Public

