

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 S. Market, Room 2078  
Topeka, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.195.21015.0000

API NUMBER 15-1854 1000

LEASE NAME Willcut

WELL NUMBER 3-1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 4 TWP. 21S RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed         

Plugging Commenced 8-25-98

Plugging Completed 8-27-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Smokey Valley Resources, Inc.

ADDRESS 1325 Hwy. 56 Lyons, Kansas 67554

PHONE# (316) 257-5529 OPERATORS LICENSE NO. 32081

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Richard Lacey (XCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3542'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	283'	None
				4-1/2"	3539'	1805'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from          feet to          feet each side. Ran 2 sks. cement on top of CIBP set @3360', shot pipe @2017', 1805', pulled up to 750', pumped 10 sks. gel and 50 sks. cement, pulled to 330', pumped 40 sks. cement, pulled to 40' and circulated cement to top. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Smokey Valley Resources, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 19 98

Irene Herzberg  
Notary Public

My Commission Expires:         

