

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15.185.00655.000 1

LEASE NAME Shaeffer Unit

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 4 TWP. 21 RGE. 13 (E) or (W)

LEASE OPERATOR Rockhold Engineering, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE# (316) 792-2506 OPERATORS LICENSE NO. 5111

COUNTY Stafford

Date Well Completed 4-29-55

Character of Well Injection

Plugging Commenced 9-18-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-28-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3605'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	217'	None
				4-1/2"	3603'	2,085.80'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3350' and 4 sacks cement. Shot casing at 2050'. Pulled 66 joints of 4-1/2" casing. BJ Titan squeezed well with 300 lbs hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100 lbs. hulls, released plug and pumped 125 sacks 60/40 poz-mix cement with 6% added gel. Maximum pressure was 300 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
 (Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 2th day of October, 1987

My Commission Expires:

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91

Notary Public

OCT 8 1987