

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-10541-0001

LEASE NAME Koopman

WELL NUMBER #2

SPOT LOCATION NW NE SW

SEC. 4 TWP 21S RGE 13W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 9-23-86

Plugging Completed 9-29-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling Purchased F/Kansas Gas
ADDRESS P.O. Box 347 Chase, Kansas 67524 Purchasing

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3607'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	812'	none
				7"	3606'	1710'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped bottom with 30 sacks cement to 2520', shot pipe @2500', 2319', 2120', 1912', 1814', 1710', pulled a total of 54 joints of 7" casing Plugged surface with 6 sacks hulls and 150 sacks econolite.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.


Mike Kelso, Vice-President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

10-15-86

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

OCT 15 1986
SUBSCRIBED AND SWORN TO before me this 14 day of October, 19 86



My Commission expires: _____

Irene Hoover
Notary Public