

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.01672.0001

API NUMBER None

LEASE NAME Willcut Unit

WELL NUMBER Tr. 2 #1

1980 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 4 TWP. 21 SRGE. 13 or (V)

COUNTY Stafford

Date Well Completed 3/24/41

Plugging Commenced 3/23/89

Plugging Completed 3/29/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? on old form if not, is well log attached? -

Producing Formation LKC 'H' Depth to Top 3396 Bottom 3400 T.D. 3565

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD STATE CORPORATION COMMISSION

4-13-89
RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out
LKC 'H'	Oil	3396	3400	8 5/8	257	-0-
				5 1/2	3467	-0-

APR 13 1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Casing parted @ 2600'. Pumped cmt plug w/220 sxs 60/40 poz w/6% gel from 2599' - surface. 3/29/89 tagged TOC @ 340'. Filled from 340'-surface w/ 1 3/4 yds ready-mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Charlotte Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 10th day of April, 19 89

Brenda K. Bowdler
Notary Public

My Commission Expires: June 27, 1990

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


15.185.01672.0000

BODINE DRILLING CO.
Willout No. 1

SEC. 4 T. 21 R. 13W.
EE $\frac{1}{2}$ NE SE

Total Depth. 3565
Comm. 3-11-41 Comp. 3-24-41
Shot or Treated.
Contractor.
Issued. 5-10-41

County Stafford.



CASING.

85/8" 257'
5 $\frac{1}{2}$ " 3467

Elevation.

Production. Pot. 2036 B.

Figures Indicate Bottom of Formations.

surface clay & sand	120
lime and shale	145
shale	220
sand	245
shale	265
red bed	743
anhydrite	774
shale	1190
shale and shells	1560
lime and shale	1730
sdy and lime	1800
lime	1870
lime and shale	1920
sand	1930
lime and shale	1985
shale grey	2035
shale and shells	2120
shale and lime shells	2260
shale and shells	2580
lime and shale	2675
shale and lime	2700
lime	2735
shale and shells	2805
lime and shale	2900
sand and shale	2930
lime	3120
lime and shale	3285
lime K.C.	3440
shale	3475
lime and shale	3550
lime	3565

Total Depth.

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1989