

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15.185.01680.0000

LEASE NAME Shaeffer

WELL NUMBER #2-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 4 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 3-15-57

Plugging Commenced 9-15-87

Plugging Completed 9-28-87

LEASE OPERATOR Rockhold Engineering, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE# (316-792-2506) OPERATORS LICENSE NO. 5111

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3584'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	240'	None
				4-1/2"	3582'	2,096.68'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3350' and 5 sacks cement. Shot casing at 2100', 2070'. Pulled 65 jts of 4-1/2" casing. B.J. Titan squeezed well with 300 lbs. hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100 lbs hulls, released plug and pumped 125 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 400 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 7th day of October, 1987

My Commission Expires:



Iona M. Leatherman
Notary Public - State of Kansas

OCT 8 1987

Form CP-4

Revised 07-86

CONSERVATION DIVISION
Wichita, Kansas