

15-185.01681-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 4 TWP. 21 RGE. 13 K/W  
Location as in quarters or footage from lines:  
SE/NW/NE

		①	

Locate Well  
correctly on above  
Section Plat.

Lease Owner Petroleum, Inc.  
Lease Name Shaeffer L-KC (Fanshier A) Well No. #2-2 (#2)  
Office Address Box 1447 - Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed December, 1957  
Application for plugging filed 12-6-82  
Plugging commenced February 12, 1983  
Plugging completed March 2, 1983  
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz  
Producing formation L-KC, Congl. Depth to top 3279' bottom 3567' T.D. 3620'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	254'	NONE
				5 1/2"	3618'	2111.58'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Dumped sand to 3350' and five (5) sacks cement.  
Shot pipe @ 2500' and 2100'.  
Pulled sixty-seven (67) joints 5 1/2" casing.  
Squeezed well with three (3) sacks hulls, fifteen (15) sacks  
gel, fifty (50) sacks cement, ten (10) sacks gel, one (1)  
sack hulls, one hundred twenty (120) sacks 50/50 pozmix cement  
with 4% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.  
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 9th day of March, 1983



Margaret Prosser  
Notary Public.

My Commission expires:

# WELL LOG

15.185.01681.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 4 T. 21S R. 13W

FARM FANSHIER "A" NO. 2


LOC. SE, NW, NE

TOTAL DEPTH 3620'

COUNTY STAFFORD CO., KANSAS

COMM. November 10, 1957 COMP. November 22, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 255' W/225 sax,  
5 1/2" @ 3618' W/100 sax.

ELEVATION 1887' DF

PRODUCTION KANSAS CITY

FIGURES INDICATE BOTTOM OF FORMATIONS

125	Surface sand & clay
165	Hard sand
752	Shale & sand
767	Anhydrite
1330	Shale & shells
1600	Shale
1685	Shale & shells
2025	Lime
2906	Shale & lime
3180	Lime
3286	Lime & shale
3501	Lime
3528	Lime & sand
3568	Conglomerate
3620	Arbuckle
3620	T. D.

RECEIVED  
STATE COMMISSION  
DEC 08 1962  
CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS }  
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #2 FANSHIER "A" well

*Verne A. Morris*

Subscribed and sworn to before me this 27th day of January 19 58

My Commission Expires: July 11, 1960

*Del J. Brown*  
NOTARY PUBLIC