

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.185.01678.0000

LEASE NAME Shaeffer

WELL NUMBER #3-3

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 4 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 12-28-56

Plugging Commenced 9-9-87

Plugging Completed 9-28-87

LEASE OPERATOR Petroleum Inc.

ADDRESS Box 1447, Great Bend, Kansas 67530

PHONE# (316-793-8968) OPERATORS LICENSE NO. 5238

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed?                      If not, is well log attached? With application

Producing Formation                      Depth to Top                      Bottom                      T.D. 3582'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	121'	None
				5-1/2"	3580'	424.43'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3350' and 5 sacks cement. Pulled 15 joints of 5-1/2" casing. B.J. Titan squeezed well with 5 sacks gel and 150 sacks 60/40 pozmix with 6% added gel. Maximum pressure was 200 psi and shutin 50 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1987

My Commission Expires:



STATE CORPORATION COMMISSION  
Igna M. Leatherman  
Notary Public  
0071 1987