


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 35 Twp. 21S Rge. 13 (W)

Location as "NE/CNW&SW" or footage from lines NW NW SW
Lease Owner Sohio Petroleum Company
Lease Name Drach Well No. 1
Office Address Box 673, Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 9-30 1948
Application for plugging filed 5-26 1965
Application for plugging approved 5-27 1965
Plugging commenced 7-2 1965
Plugging completed 7-9 1965
Reason for abandonment of well or producing formation Uneconomical



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production May 1965
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving
Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3,672 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3,670'	2,695'
				8 5/8"	237'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 3,350'; dumped 50 gallons sand. Top of sand 3,300'. Dumped 5 sacks cement. Pulled pipe. Set rock bridge at 2,337'; dumped 5 sacks cement on bridge, checked bridge at 239'. Filled to 233' with rock and to 230' with sand. Dumped 2 sacks cement with 2 1/2 gallons CACL. Filled to 228' with rock and with sand to 220'. Ran 5 sacks cement. Top of cement at 200'. Ran 20 sacks cement and mud to 40'. Set 10' rock bridge. Capped well with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

7-15-65 JUL 15 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss. W. H. Ward (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Ward

Box 673, Russell, Kansas 67665 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July, 1965

My commission expires September 27, 1967

Guadalupe Valentine Notary Public

15.185.01841.0000

CONTRACTOR'S VERIFIED LOG

Operator **Sohio Petroleum Co.** Farm Name **Drach** Well No. **1**
 Location **W¹/₄ W¹/₄ E¹/₄ Section 35-21-13**
 Pool Name **Gates** County **Stafford** State **Kansas**
 Commencement Date **9-16-68** Completion Date **9-30-68**

LOG OF WELL

Depth		Formation	Deviation from Vertical (Degrees)	Remarks
From	To			
0	5	Rig		
5	10	Cellar		
10	215	Sand & shells		
215	255	Shale & shells		
255	730	Red Bed	500'	Set 237' of 8 5/8" casing & cemented with 190 sacks cement.
730	755	Anhydrite		
755	1050	Shale	1000'	
1050	1250	Shale & shells		
1250	1340	S&S & shells		
1340	1590	Shale & shells	1500'	
1590	1885	Brk. Lime		
1885	1975	Shale		
1975	2410	Brk. Lime	2000'	
2410	2510	Shale	2500'	
2510	2645	Shale & shells		
2645	3050	Brk. Lime	All	
3050	3150	Lime & shale	O.K.	
3150	3220	Lime		
3220	3265	Brk. Lime		
3265	3570	Lime		
3570	3579	Shale (Corrected Measurement Up Hole 4 Ft.)		
3579	3613	Viola		
3613	3669	Simpson Shale		
3669	3672	Brk. Lime		

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1965

CONSERVATION DIVISION
Wichita, Kansas

Set 5 1/2" casing at 3570' or 2 Ft. off bottom. Cemented with 125 sacks cement.