


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 35 Twp. 21 Rge. 13W <sup>1/6</sup> (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NE SW  
Lease Owner Schio Petroleum Corporation  
Lease Name Drach Well No. 4  
Office Address Petroleum Bldg., Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed November 17, 1953  
Application for plugging filed November 17, - verbal 1953  
Application for plugging approved November 17, - verbal 1953  
Plugging commenced November 17, 1953  
Plugging completed November 17, 1953  
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes - verbal

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3727 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bottom plug at 240' with 25 sacks of cement  
Set top plug at 40' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mugrove Petroleum Corporation,  
Address 518 Petroleum Building, Wichita, Kansas.


STATE OF Kansas COUNTY OF Sedgwick  
I, GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1953

Alvin E. Rasmussen  
Notary Public.

My commission expires July 16, 1955.



11-24-53

CONTRACTOR'S WELL LOG

COMPANY: Sohio Petroleum Corporation  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: DRACH #4 (Sohio)  
 LOCATION: SE NE SW, Section 35-21S-13W  
 Stafford County, Kansas.  
 COMMENCED: November 4, 1953  
 COMPLETED: November 17, 1953

0	15	Sand
15	30	Sand & clay
30	230	Sand
230	715	Red bed
715	740	Anhydrite
740	1506	Shale & shells
1506	3342	Shale & lime
3342	3380	Lime
3380	3440	Lime & shale
3440	3455	Lime
3455	3505	Lime and shale
3505	3525	Lime
3525	3584	Lime and shale
3584	3645	Viola
3645	3700	Shaled lime
3700	3727	Arbuckle
	3727	Rotary Total Depth

Set 8-5/8" surface casing at 256' with 250 sacks cement.

Dry and Abandoned.

STATE OF KANSAS        )  
                                   ) SS  
 COUNTY OF SEDGWICK    )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Drach #4, SE NE SW Section 35-21S-13W, Stafford County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon Koelling  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 19th day of November 1953.

Alvin E. Rave  
 Notary Public

My commission expires July 16, 1955.

STATE OF KANSAS  
 CONSERVATION DIVISION  
 Wichita, Kansas

**PLUGGING**  
 FILE SEC 35 T 21 R 13W  
 BOOK PAGE 113 LINE 38