

15.185.01825.0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME R. C. GATES

WELL NUMBER 4

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 35 TWP. 21S RGE. 13 XXXor(W)

COUNTY Stafford

Date Well Completed 4-2-56

Plugging Commenced 3-6-86

Plugging Completed 3-6-86

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1, Dodge City

Is ACO-1 filed? on old form if not, is well log attached? ----

Producing Formation None Depth to Top ---- Bottom ---- T.D. 4185'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Water	3857	4185	10-3/4	250	-0-
				5-1/2	3857	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spotted 50 SXS cement @ 3031' and 50 SXS @ 2100'. POOH w/ Ebg. & spotted 115 SXS cement. Circ to Surf. Pumped 58 SXS down annulus. Used total 273 SXS of 60/40 poz, 6% gel & 1 SX hulls.

JOB COMPLETE.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 86

Carol Sue Brungardt

Notary Public
STATE CORPORATION COMMISSION

My Commission Expires: 2/11/89

APR - 3 1986

Form CP-4
Revised 08-84

CONSERVATION DIVISION
Wichita, Kansas

COMPANY **Herman Geo. Kaiser, Oil Producer**

BEG. 35 T. 21 R. 13W
 LOC. C SW NE

FARM **Appl-Gate** NO. 7
 (Former wall of Magnolia's - R. G. Gate #4)

TOTAL DEPTH **4185'**

COUNTY **Stafford**


COMM. **3/27/56**

COMP. **4/2/56**

SHOT OR TREATED

CONTRACTOR **Armer, Inc.**

ISSUED



CASING

20	10	250' - On old Magnolia well
15	8	
12	6	
13	5	

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Washing down	0-1980
" "	2990
" "	3610
" "	3821
" "	3828
Lime & Shale	3910
Lime	3985
Lime & Chert	4031
Lime	4185

FORMATION TOPS - On old Magnolia well

ANHYDRITE	700
CONGLOMERATE	3610
ARBUCKLE	3800
Total Depth	3810

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

[Signature]

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 19th day of April, 1956.

Rose Furey
 Notary Public

My Commission expires February 13, 1960.

MAR 5 1956

CONSERVATION DIVISION
 Wichita, Kansas