

WELL PLUGGING RECORD OR FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 863 Bitting Building Wichita, Kansas

Stafford County. Sec. 28 Twp. 21 Rge. (E) 13 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW - SW

Lease Owner Simpson Oil Company

Lease Name Keenan Well No. 1 - B

Office Address 713 First National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 10-26-42 19

Application for plugging filed 10-26-42 19

Application for plugging approved 10-26-42 19

Plugging commenced 10-26-42 19

Plugging completed 10-26-42 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Alexander

Producing formation Depth to top Bottom Total Depth of Well 3842 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Formation, Content, From, To, Size 10 3/4", Put In 153', Pulled Out None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with 14 lb. mud every 500 ft. while laying down drill pipe.

Filled from 3842 to 153' with mud.

Cement from 153' to 120'

Mud from 120 to 26'

Set bridge at 26'

Cement from 26' to 6'

Mud from 6' to top of surface

Steel plate welded over surface pipe

11-6-42

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. P. Faulkner

Address Zarah Hotel, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, SS.

Sam Payne, Jr. Employee of drilling contractor.

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature)

713 First National Bank Building, Wichita, Kans.

(Address)

SUBSCRIBED AND SWORN to before me this 4 day of November

My commission expires March 30, 1944



PLUGGING FILE SEC 28 T 21 R 13W BOOK PAGE 54 LINE 32

## KEENAN "B" 1

Operator: W. P. Faulkner  
 Contractor: Simpson & Noble, Inc.  
 Location: SW SW Sec. 28-21-13W, Stafford County, Kansas  
 Elevation: 1903' Dry  
 Commenced: 10-10-1942 Completed: 10-26-1942  
 Casing: 10 3/4" @ 150'

## LOG

Sand & Shells	80
Clay	109
Iron	112
Blue Shale & Shells	211
Shale & Shells	220
Sand	280
Red Bed	775
Shale & Shells	1400
Salt & Shale	1590
Lime	1765
Lime & Sand	1845
Broken Lime	1970
Lime	2105
Broken Lime	2280
Lime & Shale	2402
Broken Lime	2585
Shale & Shells	2655
Shale	2680
Broken Lime	2930
Shale	2935
Lime	3698
Shale	3733
Shale & Lime	3774
Shale & Chert	3807
Shale	3832
Lime	3842

SAMPLE TOPS

Elevation	1903'
Top Lansing	3395
Base K. C.	3692
Top Chert Congl.	3661
Top Viola Chert	3767
Top Simpson Shale	3799
Top Arbuckle	3832
Cored	3837-3842
No Show of Oil	

The undersigned, Sam Payne, Jr., Employee of Simpson & Noble, Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the daily drilling reports.

**PLUGGING**  
 FILE SEC 28, 21, R 13W  
 BOOK PAGE 54 LINE 22

