

15-113-21101-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-113-21,101

LEASE NAME Foth-Coering

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

990 Ft. from ~~W~~ Section Line

SEC. 35 TWP. 21 RGE. 3 (#) or (W)

LEASE OPERATOR Brunson Production Inc.

ADDRESS 200 Corporate Pl. 125 N. Emporia Wichita, Ks. 67202

COUNTY McPherson

PHONE#(316) 264-3781 OPERATORS LICENSE NO. 5350

Date Well Completed 2-27-84

Character of Well oil

Plugging Commenced 3-22-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-28-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss. Depth to Top _____ Bottom _____ T.D. 3592

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	220	8 5/8		
		0	3592	5 1/2		2004

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
fill hole to 3100 ft. with sand & dump 5' sxs. cement

Pump top with 3 hulls 10 gel & 2 hulls with 125' sxs. 50/50 pozmix 3% c.c. cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698

Address 420 5th. Box 108 Geneseo, Ks. 67444

STATE OF Kansas COUNTY OF Rice

Allen D. Nicholas (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Allen D. Nicholas

(Address) _____

SUBSCRIBED AND SWORN TO before me this 29th day of March, 19 85

Toni L. Prickett
Notary Public

My Commission Expires: December 25, 1988





Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

January 6, 1984

COMPANY: BRUNSON PRODUCTION COMPANY
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: FOTH-GOERING #1
 LOCATION: 660' FSL & 990' FWL C E/2 SW SW Section 35-21-3W
 McPherson County, Kansas
 COMMENCED: December 27, 1983
 COMPLETED: January 6, 1984
 ELEVATION:

0	to	40	Dirt & Clay
40	to	110	Sand
110	to	725	Shale
725	to	1090	Shale & Lime
1090	to	1616	Lime & Shale
1616	to	1940	Shale & Lime
1940	to	2220	Lime & Shale
2220	to	2595	Shale & Lime
2595	to	2980	Lime
2980	to	3127	Lime & Shale
3127	to	3140	Shale
3140	to	3151	Shale & Lime
3151	to	3349	Mississippi
3349	to	3449	Lime
3449	to	3543	Kinderhook Shale
3543	to	3592	Hunton
		3592	T. D.

Cut 12½" hole to 220' and run 222.28' of 8 5/8" casing, cemented with 175 sacks of cement at 220'. Plug down at 10:30 P. M., December 27, 1984. Run 3603' of 5½" casing, cemented with 150 sacks of cement at 3591', 1 foot off bottom. Plug down at 1:30 A. M., January 6, 1984.


TOPS: MISSISSIPPI - 3151' KINDERHOOK SHALE - 3449'

HUNTON - 3543'


Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Foth-Goering #1, located on 660' FSL & 990' FWL C E/2 SW/4 SW/4 Section 35-21-3W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 P. E. PLOUFFE, PRESIDENT

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 6th day of January, 1984.


 JOHNNIE L. SCHMIDT - NOTARY PUBLIC

