

JUN 17 1963

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County, Sec. 35 Twp. 21 Rge. 3 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE SW NW

Lease Owner Independent Lease Management, Company

Lease Name Goering "B" Well No. 3

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 5-28-63 19

Plugging completed 6-5-63 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3595 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202'	None
				5-1/2"	3595'	2294'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 3500' and dumped 5 sacks of cement @ 3500' with dump bailer. Pulled 5 1/2" casing. Checked fluid to 210', set rock bridge to 195' and ran 20 sacks of cement @ 195'. Mudded to 35', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1963

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1963

My commission expires May 20, 1964

Milton J. Volin
Notary Public.



BRUNSON PRODUCTION & EXPLORATION, INC.
Wichita, Kansas

WELL: GOERING "B" #3 SE SW NW
 COMMENCED RD: 4-21-58 35-21S-3W
 COMPLETED RD: 4-30-58
 TOTAL DEPTH: 3595' McPHERSON COUNTY, KANSAS
 CASING: 3595' - 5-1/2" 100 sacks cement ELEVATION: 1460 RB
 202' - 8-5/8" 120 sx. cement CONTRACTOR: Brunson P. & E., Inc.

STRATA	DEPTH	TOPS	
Surface Soil & Clay	215	Lansing	2443 (- 983)
Clay & Shale	300	Mississippi Lime	3133 (-1673)
Shale & Shells	475	Kinderhook	3437 (-1977)
Lime & Shale	590	Hunton	3535 (-2075)
Red Rock & Shale	630	Maquoketa Dolomite	3553 (-2093)
Lime & Shale	1125		
Shale & streaks of lime	1450		
Shale & Lime	2555		
Sand	2585		
Lime & Shale	2660		
Lime	2780		
Sand	2795		
Lime	3083		
Lime & Shale	3217		
Lime	3270		
Chert & Lime	3351		
Lime	3434		
Lime & Shale	3595		
Total Depth	3595		

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 20 1963
 CONSERVATION DIVISION
 WICHITA, KANSAS

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON PRODUCTION & EXPLORATION, INC.,

Ralph B. McLaughlin
 Ralph B. McLaughlin

Signed and sworn to in my presence this 4th day of June, 1958, by Ralph B. McLaughlin, Secretary-Treasurer of the Brunson Production & Exploration, Inc., a Corporation of the State of Kansas.

Mary G. LaFollette
 Mary G. LaFollette, Notary Public

My commission expires June 16, 1959.