

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION
6-29-62 JUN 29 1962
CONSERVATION DIVISION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Murfin Drg Co
Complete Address: 617 Union Center Wichita, Kansas
Lease Name Gerney Well No. 7
Location NE NW NW Sec. 14 Twp. 14 Rge. (E) (W) 20
County Ellis Total Depth 3840
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Ace Pipe Pulling
Address: Great Bend, Kans License No. 2
Operation Completed: Hour 3PM Day 27 Month 6 Year 62

The Above well was plugged as follows:

8 5/8" 298' circulated with cement - 5 1/2" 3824' with 100 sax cement - PB
& Perf 3790' - filled with sand to 3780', set 4 sax cement with dump
bailer - pulled 2500' 5 1/2" to 500', circulated hole with heavy gel mud -
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 200', displaced
20 sax cement through 5 1/2" at 200', heavy mud to 30', set bridge and 10
sax cement to bottom cellar.
Mudding and cementing by Ace Pipe Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9/9/62
INV. NO. 5308-W