

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pentagon Corp

Complete Address: 501 Petroleum Bldg Wichita, Kansas

Lease Name Schlyer Well No. 1

Location NW NW NW Sec. 1 Twp. 14 Rge. (E) (W) 20

County Ellis Total Depth 3920

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: National Drg Co

Address: Wichita, Kansas License No.

Operation Completed: Hour 11AM Day 12 Month 4 Year 63

The Above well was plugged as follows:

8 5/8" 217' circulated with cement.

Circulated hole with heavy mud, set plug at 600', displaced 20 sax
cement through drill pipe, heavy mud to 200', set plug and displaced 20
sax cement through drill pipe, heavy mud to 35', set plug, 1/2 sack hulls
and filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Letty
Well Plugging Supervisor

DATE 4/15/63
INV. NO. 6899-U