



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NW

SEC. 6 TWP. 14 RGE. 19

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Strohmeier

Operator Prime Drg Co Address Wichita, Kans

*3111 APCO TOWER BLDG.
TULSA, OKLA*

Field _____ County Ellis

Total Depth 3966 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 164' circulated with cement - 5 1/2" at 3950, 150 sax
behind pipe.

Lane-Wells plugs to 3944 and 3650' - Top perforations at
3613', filled with chat to 3610', run 5 sax cement with dump
bailer - pulled 3200' of 5 1/2", mudded hole to 164', set wood plug,
rock bridge and 15 sax cement, mudded hole to 35', set wood plug
and 10 sax cement, to bottom cellar.

District Conservation Agent

Date 1-20-50

PLUGGING
FILE SEC 6-114 R19W
BOOK PAGE 135 LINE 27

1-24-50 JAN 24 1950

ST. ...
CON ...
...
F