

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 28 TWP. 14 RGE. 20

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Fisher

Operator Herman Kaiser & Francis Oil ^{+Gas} Address 909 Palace Bldg Tulsa, Okla

Field _____ County Ellis

Total Depth 3810 Feet.

Plugging Contractor H 30 Drg Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 255' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at
300', displaced 25 sax cement through drill pipe at 300', heavy
mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement
to bottom cellar.

District Conservation Agent

Date 6-15-57

RECEIVED
STATE CORPORATION COMMISSION
6-24-57
JUN 24 1957

PLUGGING
FILE SEC. 28 T. 14 R. 20 W
BOOK PAGE 22 LINE 38

CONSERVATION DIVISION
Wichita, Kansas