

8

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SW

SEC. 21 TWP. 13 RGE. 20

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Schumacher

Operator Gulf Oil Co Address Box 544 Chase, Kans

Field _____ County Ellis

Total Depth 5882 Feet.

Plugging Contractor C. E. Shull

Plugging Contractor's License No. 8

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1574' circulated with 775 sax cement - 5 1/2" at 5859' with 100 sax cement behind.

Cement to 5859', perforated at 5852' - run 6 sax cement with dump bailer - pulled 3180' 5 1/2" - filled hole with heavy mud to 500', set rock and 15 sax cement - mud to 55', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
2-23-55
FEB 23 1955
CONSERVATION DIVISION
Wichita, Kansas

E. E. Perry
District Conservation Agent

Date 2-18-55

PLUGGING
FILE SEC 21 / 13 R 20W
BOOK PAGE 20 LINE 29