

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
APR 11 1966
4-11-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil Company

Complete Address: 780 Fourth Nat. Bldg. Wichita, Kansas.

Lease Name King Well No. 7

Location C & SW - SW Sec. 7 Twp. 15 Rge. 20 (E) (W) X

County Ellis Total Depth 4000

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co Tools

Address: License No.

Operation Completed: Hour 11:30 P Day 9 Month April Year 1966

The Above well was plugged as follows:

Total Depth 4000' 8 5/8 set at 2447. CW 125 cu. Perm. Circ.

Gunned pits circulated hole with heavy mud, set cementing plug at 650 ft.,

and displaced 30 sax cement thru drill pipe, heavy mud to 240 ft., set

cementing plug and displaced 20 sax cement thru drill pipe, heavy mud to 40 ft.,

set cementing plug, 1/2 sac hulls and 10 sax cement, cementing to base of cellar.

Plug Rat hole with 2 Sax. Cem. By Halib. Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4/12/66

INV. NO. 3031-u