

15.051.30261.00.00

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. COOK of EMPERIAL OIL has this
date requested permission to plug the following described well:

Mr. COOK guarantees payment of the plugging fee.

Operator's full Name: EMPERIAL OIL CO.

Complete Address: 780 Fourth Nat. Bldg, Wichita Kan.

Lease Name: KING Well No. 1

Location: C-SW-SW Sec. 7 Twp. 15 Rge. 20 (E)(W) 1

County ELLIS Total Depth 4000 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. COOK was instructed to plug the well as follows:

Jett pits circulate hole with heavy mud, set cementing plug at 650 ft.,
and displace 30 sac cement thru drill pipe, heavy mud to 240 ft., set
cementing plug and displace 20 sac cement thru drill pipe, heavy mud
to 40 ft., set cementing plug, 1/2 sac hulls and 10 sac cement, cementing
to base of cellar. Plug rat hole with two sac cement. By Halib. Cen. Co.

Very truly yours,

L. J. Messing
Conservation Division Agent