

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Kansas

Lease Name Seeyle "B" Well No. 3

Location NW SE SW Sec. 35 Twp. 15 Rge. 19 (E) (W) X

County Ellis Total Depth 3304

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 2:15 P Day 27 Month 6 Year 1968

The Above well was plugged as follows:

RTD 3304' 8 5/8 csg set at 1231' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 30 sc cem.
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/2/68
INV. NO. 8032-6

RECEIVED
STATE CORPORATION COMMISSION
Signed: _____
JUL 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Geo. J. Messing
Well Plugging Supervisor