

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE SE SE

SEC. 20 TWP. 15 RGE. 18

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Weisner "A"

Operator Artnell Co Address 553 Pet Bldg Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3610 Feet.

Plugging Contractor Leben Drgv Co & Halliburton Cementing Co

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

15" at 104' circulated with cement - 8 5/8" at 1110' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 500', displaced 50 sax cement through drill pipe, heavy mud to 250', set cementing plug and displaced 30 sax cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Cementing by Halliburton Co.

District Conservation Agent

Date 10-28-57

STATE CORPORATION COMMISSION  
OCT 31 1957 10-31-57  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING  
FILE SEC. 20 T. 15 R. 18 W  
BOOK PAGE 58 LINE 17