

State of Kansas



ROBERT B. DOCKING
DALE E. SAFFELS
JULES V. DOTY
JAMES O. GREENLEAF
RAYMOND B. HARVEY
JACK GLAVES

Governor
Chairman
Commissioner
Commissioner
Secretary
Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

August 10, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Pat Simmons

Complete Address: 5252 N. Broadway, Wichita, Kansas 67219

Lease Name: Duvall Well No. 3

Location: SW NE SW Sec. 2 Twp. 21 Rge. 6 (E)(W) X

County: Rice Total Depth 3404' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Simmons was instructed to plug the well as follows:

Fill hole with sand to 3360' and cement with 6 sacks cement.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and cement
hole with 30 sacks cement. Fill hole with mud to 40'. Set rock bridge
from 40' to 30' and cap hole with 15 sacks cement.

Very truly yours,

Arthur J. Loman
Conservation Division Agent