



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

September 7, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling Inc. has this
date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: Commercial Oil Company

Complete Address: 5252 North Broadway, Wichita, Kansas 67218

Lease Name: Duvall Well No. 1

Location: SW NW SW Sec. 2 Twp. 21 Rge. 6 NE (E) (W) X

County: Rice Total Depth 3398' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Comstock was instructed to plug the well as follows:

Fill hole with sand to 3375' and cement with 6 sacks cement.

Fill hole with mud to 215'. Set rock bridge from 215' to 200' and

cement hole to base of cellar with 4½ yards ready-mix concrete.

Very truly yours,

Conservation Division Agent