



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 6, 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1964

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bert Self of Bert Self Casing Pulling has this

date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: H. C. Bennett

Complete Address: 1212 Union Nat'l Bldg., Wichita, Kansas

Lease Name: Chilvers Well No. 2

Location: SW SW SW Sec. 2 Twp. 21 Rge. 6 (W) X

County Rice Total Depth 3404 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3390' and cement with 5 sacks.

Fill hole with mud to 165'. Set rock bridge from 165'

to 150' and cement hole to base of cellar with 3 yards

ready mix cement.

Very truly yours,

Conservation Division Agent