

(Copy)

State of Kansas



15.159.05205.0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

March 21, 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 127, Sterling, Kansas

Lease Name: White "C" Well No. 1

Location: C NW NE NE Sec. 2 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3420' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3380' and cement with 5 sacks.

Fill hole with mud to 200'. Set rock bridge from 200' to

190' and cement with 25 sacks. Fill hole with mud to 40'.

Set rock bridge from 40' to 30' and cap hole with 10 sacks

cement.

RECEIVED  
STATE CORPORATION COMMISSION

Very truly yours,

APR 19 1963

William J. Leonard  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas