



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

WICHITA, KAN.

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ray Rice of Sterling Drilling Co. has this

date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: P.O. Box 127, Sterling, Kansas

Lease Name: White "C" Well No. 3

Location: E/2 SE NE Sec. 2 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3399' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 155'. Push
plug and 1/4 sack hulls to 155' and cement with 20 sacks
through drill pipe. Fill hole with mud to 35'. Push
plug and 1/4 sack hulls to 35' and cap hole with 10 sacks
cement. Bridge, and cement rathole with 2 sacks.

Very truly yours,

Albert J. Leonard
 Conservation Division Agent