

State of Kansas



15.185.12088.0001 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Elmo Finch of Pipe Pullers Inc. has this

date requested permission to plug the following described well:

Mr. Finch guarantees payment of the plugging fee.

Operator's full Name: F. G. Holl

Complete Address: 6427 E. Kellogg, Wichita, Kansas

Lease Name: Snider Well No. # 1

Location: App. E/2 SE NW Sec. 3 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3439 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Finch was instructed to plug the well as follows:

255' of 8 5/8" surface pipe cement circulated with 200 sacks.

3439' of 4 1/2" long string cemented with 50 sacks. Plugged back

to 3160'. Perferated 3110' to 14'. Sanded to 3100', cemented

with 3 sacks. Fill hole with mud to 225', 10' rock bridge,

cement with 20 sacks. Fill hole with mud to 40', 10' rock

brdige, cement with 10 sacks to base cellar.

Very truly yours,

Audie Elving
Conservation Division Agent