

State of Kansas



15.185.20052.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed August 4, 1967.

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Inc.

Complete Address: 1101 Wichita Plaza Bldg., Wichita, Ks. 67202

Lease Name: Snider Well No. # 1

Location: SW NE NE Sec. 3 Twp. 21 Rge. 11 (E)(W) W

County Stafford Total Depth 3410' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

252' of 8 5/8" surface pipe, cement circulated with 375 sacks. Fill
hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Aubrie Elving
Conservation Division Agent