

*R*

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 8 1961  
CONSERVATION DIVISION  
Wichita, Kansas

11-8-61

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: McPherson

Location: NW-NE-SE- Sec. 17 Twp. 21 Rge. 1 NE (W) \_\_\_\_\_

Name of Field: Graber-E Total Depth: 3332'

I have this date completed supervision of plugging of:

Lease Name: Goering Well No. 9

Operator's Full Name: Alfred Koehn

Complete Address: Galva, Kansas.

Plugging Contractor Art Lamb Casing Pulling Co.

Address: Box 983, Hutchinson Kansas. License No. 440

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3:PM Day 24 Month 10 Year 61

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3332' back to 3310' ran 7 sack cement w/ dump bailer.

Ripped off and pulled 7" casing. Filled hole w/ mud from 3275' back to 160' set a 10"

rock bridge and ran 3 1/2 yards of ready mix cement back to zero. 10" surface pipe 5'

below ground level.

Signed: *Robert M. Jones*  
Conservation Division Agent

Reviewed: *Harold H. Jones*  
Field Supervisor

Remarks:

INVOICED

DATE 11-13-61

INV. NO. 4512-E