

15.145.00785.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 1 - 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Fairbanks Well No. 1

Location SE SE NW Sec. 34 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3941'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3 P Day 30 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3941' 8 5/8 csg set at 943' cwc

5 1/2 csg set at 3939' cw 150 sk cmt.

5 1/2 csg PBTD 3700' with top perf. (3521)

Set 5 1/2 wood plug at 3500' -poured 10' sand -dumped 4 sk cmt W/dump bailer. (3460-3500)

~~Cutoff and recovered 2660' of 5 1/2 csg.~~

Cutoff & recovered 1955' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 325' -set rock & sand bridge (325-300)

Filled with readymix cement from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Murray
Well Plugging Supervisor

INVOICED

DATE 4/2/74

INV. NO. 8835-W