

15.145.00799.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Wieman Well No. 4

Location S/2 NW NW Sec. 34 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3845'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas 67530 License No. 399'

Operation Completed: Hour 2 P Day 25 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3845' 8 5/8 csg set at 992' cwc

5 1/2 csg set at 3844' cw 150 sk cmt.

Filled 5 1/2 csg W/sd to 3800' -poured 10' sd -dumped 4 sk cmt W/dump bailer. (3760-3800)

Cutoff and recovered 3002' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 425' -set rock & sand bridge (425-375)

Filled with readymix cement from 375' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo L. Massey
Well Plugging Supervisor

DATE 3/28/74

INV. NO. 8818-10