

15.145.01429.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Fairbanks Well No. 4

Location NE SE NW Sec. 34 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3863'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1 P Day 14 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3863' 10 3/4 csg set at 1000' cwc 650 sk.

7" csg set at 3844' cw 200 sk cem.

Filled 7" csg W/sd (3825-3863) dumped 5 sk cem W/dump bailer. (3795-3825)

Cutoff and recovered 1437' of 7" csg.

Filled 20 3/4 csg with mud to 460' -rock & sand bridge (460-400)

Filled with readymix cement from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/18/74
INV. NO. 8768-U

Signed: Leo F. Messing
Well Plugging Supervisor