

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Fairbanks Well No. 3

Location NW SE NW Sec. 34 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3848'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 12 M Day 30 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3848' 8 5/8 csg set at 1000' cwc.

5 1/2 csg set at 3841' cw 150 sk cmt.

5 1/2 csg PBSD 3820' with top perf. (3801')

Filled 5 1/2 csg with sand to 3775' -poured 10' sand & dumped 4 sk cmt W/dump bailer.

Cutoff & recovered 2830' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 325' -set rock & sand bridge (325'--300')

Filled with readymix cement from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 4/2/74

INV. NO. 8836-W